



- LEGEND:**
- Existing asphalt pavement
 - Proposed asphalt pavement
 - Proposed grass
 - Proposed concrete edging
 - Proposed white road marking
 - Proposed yellow road marking
 - Proposed timber fence TF
 - Proposed sign on new post
 - Proposed timber bollard
 - Relocated timber bollard
 - Proposed cycle repair station. See note 8.
 - Proposed parking charge machine. See note 5.
 - Relocated cycle stands with mount
 - Relocated litter bin
 - Relocated memorial seat
 - Proposed ditch. For details refer to Drg. 100007748-TH-4-0510
 - Proposed attenuation pond. For details refer to Drg. 100007748-TH-4-0510

- NOTES**
1. All measures are in metres unless otherwise stated.
 2. Sign faces and elements of street furniture are not to scale.
 3. Manual dig excavations to be carried out in root protection areas.
 4. No resurfacing of the existing car park is required as part of these works. Localised potholes to be repaired. Refer to drawing 100007748-4-TH-1100-01 for details.
 5. Contractor to liaise with the chosen supplier for phasing of the works to install the paying machine. Foundation of paying machine TBC by chosen supplier.
 6. All levels are in metres above ordnance datum unless stated otherwise. Survey is in OSGB36 datum and coordinates, computed using RTK GPS corrections to the OSGM(15) GEOID model, as supplied by MHB Consultants. Survey undertaken in October 2021.
 7. Final arrangement of all relocated and proposed street furniture to be agreed on site with the car park officer.
 8. Cycle Repair Station comprised of bike repair stand and bike pump both in brushed finish Stainless Steel secured as per manufacturer's recommendations. Tool Tethers: 4mm stainless steel cable. Hand Tools: Phillips and flat head screwdrivers, 2.5, 3, 4, 5, 6, 8mm Allen keys, adjustable spanner star drive multi – tool, 8, 9, 10, 11mm multi spanners, 2 Tyre lever.
 9. Natsol Toilet, Double Zero-Discharge Type 2, Wooden Building (dimensions 1.9m x 2.46m x 2.24m). The two units to be in one double building, complete width of building to be 1.9m + 1.9m + 0.05m (gap) = 3.85m. Contractor shall liaise with toilet supplier and ensure the supply and installation of the toilets is integrated within the overall works programme.

Rev	Date	Description	Drm	Chk	App
2	JUL 2022	PROPOSED TIMBER FENCE AND LARGE PARKING BAY	ND	NC	VR
1	MAY 2022	FOR APPROVAL	ND	NC	VR
0	JAN 2022	FOR APPROVAL	HP	NC	DR

This drawing has been specifically prepared to meet the requirements of the named client and may contain design and innovative features which differ from conventional design standards.



Client
EDINBURGH
 THE CITY OF EDINBURGH COUNCIL

Project
 CITY OF EDINBURGH COUNCIL
 PENTLAND HILLS REGIONAL PARK
 CAR PARK DESIGN

Drawing Title
 THREIPMUIR CAR PARK
 GENERAL ARRANGEMENT

Drawing Status
FOR APPROVAL

Drawn	Designed	Date	Scale	Size
HP	NC	JAN 2022	1:250	A1

Drawing No. 100007748-4-TH-0100 Rev 2

SAFETY, HEALTH AND ENVIRONMENTAL INFORMATION
 In addition to the hazards/risks normally associated with the type of work detailed on this drawing, note the following significant risks and information identified by the designer

HAZARD
 H001 POTENTIAL PRESENCE OF WILDLIFE - CONTRACTOR TO INSPECT AREAS OF NEW CONSTRUCTION FOR ANY RISKS TO WILDLIFE THROUGH EXCAVATION.

H002 POTENTIAL RISK OF TREE INSTABILITY - CONTRACTOR TO ASSESS THE STABILITY OF TREES WHILE HAND-DIGGING.

H003 POTENTIAL RISK OF TREE ROOTS DAMAGE.

It is assumed that all works be carried out by a competent contractor working, where appropriate, to an approved method statement.

TRAFFICKED FACE OF THE PROPOSED TIMBER FENCE TO BE INSTALLED 0.45 METRES TO THE BACK OF THE EDGING. CONTRACTOR TO ENSURE THE EXISTING TREES' ROOT SYSTEMS ARE NOT DAMAGED WHEN CONSTRUCTING THE FENCE. CONTRACTOR SHALL AGREE THE INTRODUCTION OF GAPS IN THE FENCE TO AVOID EXITING TREES' STEMS WITH THE CAR PARK OFFICER.

TRAFFICKED FACE OF THE PROPOSED TIMBER FENCE TO BE INSTALLED 0.45 METRES TO THE BACK OF THE EDGING. CONTRACTOR TO ENSURE THE EXISTING TREES' ROOT SYSTEMS ARE NOT DAMAGED WHEN CONSTRUCTING THE FENCE. CONTRACTOR SHALL AGREE THE INTRODUCTION OF GAPS IN THE FENCE TO AVOID EXITING TREES' STEMS WITH THE CAR PARK OFFICER.

3 NO. TIMBER BOLLARDS TO BE TAKEN FROM STORE AND RELOCATED

PROPOSED NO.3 TIMBER BOLLARDS TO STOP ILLEGAL PARKING

EXISTING CYCLE STANDS AND MOUNT TO BE TAKEN FROM STORE AND RELOCATED

PROPOSED CYCLE REPAIR STATION. SEE NOTE 8.

PROPOSED PARKING CHARGE MACHINE

EXISTING CYCLE STAND TO BE RETAINED

2 NATSOL TOILETS. SEE NOTE 9.

EXISTING SOIL TO BE RE-PROFILED TO ALLOW THE INSTALLATION OF THE PROPOSED TOILETS.

P Motor-homes, horse vehicles and minivans



PS03 & PS04

2 NO. MEMORIAL SEATS TO BE TAKEN FROM STORE AND RELOCATED

ONE WAY SYSTEM TO BE SIGN POSTED

LITTER BIN TO BE TAKEN FROM STORE AND RELOCATED

P Disabled badge holders only

PS01 & PS02

EXISTING GRIT BOX TO BE RETAINED

2.4m 1.2m 4.8m 12.4m

P Disabled badge holders only

PS07 & PS08

P Motor-homes, horse vehicles and minivans

PS05 & PS06

PS09

H001

H002

H003

H001

H002

H003

H001

H001

H002

H003

H002

H003